

# TRIPLE WIDE CARPORT

26' - 30' WIDE



Vertical Style

## VERTICAL STYLE ROOF

26x21	28x21	30x21
\$3,745	\$3,895	\$4,045
26x26	28x26	30x26
\$4,495	\$4,695	\$4,895
26x31	28x31	30x31
\$5,695	\$5,895	\$6,195
26x36	28x36	30x36
\$6,395	\$6,645	\$6,995
26x41	28x41	30x41
\$7,195	\$7,445	\$7,795
26x46	28x46	30x46
\$8,095	\$8,345	\$8,695
26x51	28x51	30x51
\$8,795	\$9,045	\$9,395

## BOXED STYLE ROOF

26x21	28x21	30x21
\$2,945	\$3,095	\$3,245
26x26	28x26	30x26
\$3,595	\$3,795	\$3,995
26x31	28x31	30x31
\$4,195	\$4,395	\$4,595
26x36	28x36	30x36
\$4,795	\$5,195	\$5,495

## Standard Features GA, KY, NC, SC, TN, VA, WV

- 29 Gauge Metal Roofing
- 14 Gauge Galvanized Steel Framing
- 5' On-Center Leg Spacing
- 6' Standard Leg Height
- Standard Welded Truss
- Bracing on Every Roof Peak
- Bracing on Every Leg
- Ground, Concrete, or Asphalt Anchoring
- 17 Color Choices: Roof, Sides and Trim

*If a 7K lull lift is required for installation, CBS can provide a lift for an additional \$3,750.*

YOUR PREMIER STEEL BUILDING CHOICE

Address:  
510 Riverside Dr  
Mt. Airy NC 27030

Website:  
CustomBuiltStructures.com

Phone:  
877-552-7020



Boxed Style

*\*Prices are subject to change without notice and may be subject to surcharge. Check our website for current information.  
\*Return trip and labor fee will be added to any additional order. \*Orders over \$7,500 require site pictures prior to scheduling install.*

## 26'-30' Optional Features

	21'	26'	31'	36'	41'	46'	51'
12 Gauge 26'-30' Wide	\$420	\$525	\$625	\$725	\$825	\$930	\$1,020
4' On Center	\$380	\$505	\$630	\$760	\$885	\$1,110	\$1,135
4/12 Roof Pitch	\$820	\$1,010	\$1,170	\$1,395	\$1,575	\$1,765	\$1,935
5/12 Roof Pitch	\$920	\$1,100	\$1,270	\$1,495	\$1,675	\$1,865	\$2,035
6/12 Roof Pitch	\$1,020	\$1,210	\$1,370	\$1,595	\$1,775	\$1,965	\$2,135
1' Side Overhang	\$440	\$570	\$690	\$810	\$940	\$1,050	\$1,170

## Side Height

HEIGHT	21'	26'	31'	36'	41'	46'	51'
7'	\$80	\$100	\$120	\$140	\$160	\$180	\$200
8'	\$160	\$200	\$240	\$280	\$320	\$360	\$400
9'	\$240	\$300	\$360	\$420	\$480	\$540	\$600
10'	\$320	\$400	\$480	\$560	\$640	\$720	\$800
11'	\$400	\$500	\$600	\$700	\$800	\$900	\$1,000
12'	\$480	\$600	\$720	\$840	\$960	\$1,080	\$1,200
13* Single Reinforced	\$1,000	\$1,200	\$1,400	\$1,600	\$1,800	\$2,000	\$2,200
14* Single Reinforced	\$1,200	\$1,400	\$1,600	\$1,800	\$2,000	\$2,200	\$2,400

## Close Both Sides

HEIGHT	21'	26'	31'	36'	41'	46'	51'
6'	\$560	\$685	\$810	\$935	\$1,060	\$1,185	\$1,310
7'	\$775	\$925	\$1,075	\$1,225	\$1,375	\$1,525	\$1,675
8'	\$785	\$945	\$1,110	\$1,275	\$1,440	\$1,605	\$1,770
9'	\$800	\$975	\$1,150	\$1,325	\$1,500	\$1,675	\$1,850
10'	\$1,010	\$1,215	\$1,420	\$1,625	\$1,830	\$2,035	\$2,240
11'	\$1,045	\$1,265	\$1,485	\$1,705	\$1,925	\$2,145	\$2,365
12'	\$1,075	\$1,310	\$1,545	\$1,780	\$2,015	\$2,250	\$2,485
13'	\$1,295	\$1,550	\$1,815	\$2,080	\$2,345	\$2,610	\$2,875
14'	\$1,305	\$1,570	\$1,850	\$2,130	\$2,410	\$2,690	\$2,970
Vertical Sides 6'-10'	\$400	\$500	\$600	\$700	\$800	\$900	\$1,000
Vertical Sides 11'-14'	\$600	\$750	\$900	\$1,050	\$1,200	\$1,350	\$1,500
Vertical Wainscoting	\$325	\$400	\$550	\$550	\$625	\$700	\$775

## Closed One End ( Per End)

HEIGHT	26' Wide	28' Wide	30' Wide
6'	\$1,200	\$1,275	\$1,350
7'	\$1,325	\$1,475	\$1,625
8'	\$1,375	\$1,525	\$1,675
9'	\$1,425	\$1,575	\$1,725
10'	\$1,600	\$1,800	\$2,000
11'	\$1,625	\$1,840	\$2,050
12'	\$1,650	\$1,87	\$2,100
13'	\$1,850	\$2,025	\$2,200
14'	\$1,900	\$2,075	\$2,250
Vertical 6'-10' (Per End)	\$350	\$375	\$400
Vertical 11'-14' (Per End)	\$375	\$400	\$425
Vertical Wainscoting	\$450	\$525	\$600
If unit is 12 Gauge add	\$100	\$130	\$160
If unit is 4' on center add	\$220	\$260	\$290

\*Prices are subject to change without notice and may be subject to surcharge. Check our website for current information.  
\*Return trip and labor fee will be added to any additional order. \*Orders over \$7,500 require site pictures prior to scheduling

Extra Panels	Horiz / Vert.	J-Trim*
21'	\$130 / \$260	\$55
26'	\$150 / \$290	\$65
31'	\$170 / \$310	\$75
36**	\$190 / \$330	\$85
41**	\$250 / \$390	\$95
46**	\$270 / \$410	\$105
51**	\$290 / \$430	\$115

\*Both Sides \*\*Not a continuous Panel

Roll Up Doors	Manual	Motor**
6x7	\$550	\$715
8x8	\$625	\$820
9x8	\$700	\$910
10x8	\$750	\$975
10x10	\$900	\$1,300
12x12	\$1,500	\$2,000
14x14 *	\$2,940	\$3,250

\*Lift required.

\*\* Must charge for Frame-Out for all Roll Up Doors with Motor.

\*\*Roll Up Doors with Motors must be on Mayberry Overhead Doors order form and is installed separate after building installation.

## Frame Outs Sides or Ends Must be Closed

Walk In Door	\$100	36"x80"
Window	\$90	30"x36"

## 45\* Trim Kit- Dutch Openings

Per Opening	\$80
Must Closed Sides or Ends	

## Lean To Connection on End

12'-22'	24'-30'	32'-40'
\$300	\$400	\$500

## Color Screws

Roof(Base)	Add 3%
Sides/Ends	Add 3%

## Side Connection Per Side

21'L	26'L	31'L	36'L	41'L	46'L	51'L
\$125	\$140	\$160	\$180	\$200	\$220	\$240

## Anchors

Extra Mobile Home/Asphalt Anchors :	\$30
-------------------------------------	------

## Extra Panels

Trimmed Half Panels	21'L	26'L	31'L	36'L	41'L	46'L	51'L
Both Sides - Cannot be split	\$210	\$240	\$270	\$310	\$360	\$450	\$480

## Extra Bows

26'-30'	\$300
---------	-------

6' Inc.  
Add \$ 15/ft  
14' Max

## Concrete Dimensions

All Concrete Pads are Recommended to pour 3" wider on all sides.  
Units 18x20 need to have 18'6"x20'6" Cement Pad

Refer to Concrete Detail Page in Generic Plans\* Provided upon Request

## 5" Seamless Gutters (Up to 100')

\*\* Only offered within 3-Hour Radius of Mount Airy, North Carolina \*\*

\$15/White Gutters \$20/Color Gutters

1 Downspout every 50-ft included, Extra Downspout \$100/ea. Leaf Guard is \$10/Ft Extra.

2 Week Lead Time / No Discounts / No Commission / Must be on separate order form.

Must be Paid in Full Before Install. No Labor Fee Under 14' tall.

## NOTES: